



Request for Tender

CSIORFT2026019 - Ground
Maintenance Services for
CSIRO Managed Sites VIC
Metro

Attachment A Statement of Requirements

Contents

1. STATEMENT OF REQUIREMENTS	3
1.1. Scope	3
1.2. Background.....	3
1.3. Mandatory Requirements	3
1.4. Requirements	3
1.5. Grounds Services	4
1.6. Seasonal Preparedness.....	7
1.7. Incident Response Periodic and Reactive Services	7
1.8. Equipment	8
1.9. Staffing and Personnel	9
1.10. Keys and Access Cards.....	9
1.11. Prevention of Disturbance	10
1.12. Standards and Certifications	10
1.13. Performance	10
1.14. Reporting	11
1.15. Meetings.....	12
1.16. Service Delivery Plan	13
1.17. Transition In / Transition Out	13
1.18. Sustainable Procurement	13
1.19. HSE Requirements	14
1.20. Supply Chain Integrity	15
1.21. Broader Economic Benefits to the Australian Economy	15
1.22. Asbestos	16

1. Statement of Requirements

1.1. Scope

- 1.1.1. CSIRO, through this RFT, is seeking responses from suitably qualified and experienced service providers to provide grounds maintenance services at its Clayton Precinct (Clayton, Clayton North and Notting Hill), Aspendale, and Werribee (Sneydes Road and South Road).
- 1.1.2. The Contractor shall provide comprehensive preventive and reactive grounds maintenance and landscaping services to ensure all outdoor areas at the mentioned sites are maintained to a high standard of safety and presentation.

1.2. Background

- 1.2.1. CSIRO operates an extensive portfolio of buildings and facilities across Australia. Through this RFT, CSIRO is seeking Ground Maintenance Services for the Site locations outlined in Table 1 CSIRO Regions and Site locations to ensure CSIRO maintains its obligations under the relevant statutes and regulations and provides a safe working environment for all staff.
- 1.2.2. CSIRO has a requirement for the provision of the Services in the Victorian region for their Aspendale, Clayton Precinct (Clayton and Clayton North, Notting Hill), and Werribee Sneydes Road and South Road sites

1.3. Mandatory Requirements

- 1.3.1. Tenderers must attend all site visits for the below sites:

CSIRO Site Name	Site Address
Clayton	Research Way, Clayton VIC 3168
Clayton North	71 Normanby Road, Clayton VIC 3168
Clayton, Notting Hill	5 - 7 Commercial Drive, Notting Hill VIC 3168
Aspendale	107 - 121 Station Street, Aspendale VIC 3195
Werribee Sneydes Road	671 Sneydes Road, Werribee VIC 3030
Werribee South Road	6 South Road, Werribee VIC 3030

- 1.3.2. Additional information can be found at Item 5.11 of the Head Document.

1.4. Requirements

- 1.4.1. The Contractor will be required to deliver Grounds Maintenance Services at the sites detailed in Table 1 CSIRO Regions and Site locations.

Table 1 CSIRO Regions and Site locations			
Region	CSIRO Site Name	Site No.	Site Address

CSIRORFT2026019 - Ground Maintenance Services for CSIRO Managed Sites VIC Metro

Victoria	Clayton	6040	Research Way, Clayton VIC 3168
	Clayton North	6300	71 Normanby Road, Clayton VIC 3168
	Clayton, Notting Hill	6280	5 - 7 Commercial Drive, Notting Hill VIC 3168
	Aspendale	6020	107 - 121 Station Street, Aspendale VIC 3195
	Werribee Sneydes Road	6320	671 Sneydes Road, Werribee VIC 3030
	Werribee South Road	6310	6 South Road, Werribee VIC 3030

1.4.2. The Contractor will be required to undertake:

- (a) Grounds Maintenance services to ensure CSIRO sites are maintained in an acceptable general appearance, are safe to access, and that the tenderer is competent and has the required capability to service our sites.
- (b) Ensure reception entries are priority areas and are to be kept to CSIRO standards.
- (c) Services whereby the maximum time between site visits is two weeks, to ensure litter and weed control is at an acceptable level.

1.4.3. The Contractor is to undertake Services within the working hours below:

- (a) Clayton Precinct, Werribee Sneydes & Aspendale:
 - i. Monday to Friday, 7:30am to 6:00pm (except for public holidays)
- (b) Werribee South Road:
 - i. Ad-hoc basis only Monday to Friday advised by CSIRO Facility Manager

1.4.4. In undertaking the services, the Contractor should comply with local council, State Government and Commonwealth laws, regulations and safety codes, including but not limited to, Workplace Health and Safety, noise restrictions and workhour restrictions.

1.5. Grounds Services

1.5.1. Lawn Maintenance

- (a) Mowing – Mow all lawn areas evenly to a height between 30-50mm
- (b) Edging - Lawns trimmed to form a defined edge using a mechanical edger along pathways, kerbing, gutters, and around buildings, posts and garden beds and fences. No chemicals to be used as an edging alternative unless approved in writing by the CSIRO Facilities Contact;
- (c) Mowing/edging clean-up – Grass clippings must not be allowed to build up on lawn areas. Sweep all grass clippings from adjacent roads, paths, hard surfaces immediately after mowing and edging. All green waste to be removed off site to a registered recycling facility;

CSIRORFT2026019 - Ground Maintenance Services for CSIRO Managed Sites VIC Metro

- (d) Litter pick – Pick up litter and general waste (e.g. paper, bottles, plastic, cans, etc.) from all lawn areas. Sort and place in recycling and waste bins provided by CSIRO on site;
- (e) Leaf fall – Remove leaves from all lawn areas and recycle at a registered facility off site;
- (f) Weed control – Broadleaf weed spray all lawn areas, as needed at least twice per year, when requested by the CSIRO Facilities Contact. Herbicides must comply with Australian Standards and be approved, in writing, by the CSIRO Facilities Contact. A record of chemical application will need to be kept and presented to the CSIRO Facilities Contact as part of all spraying events onsite.

1.5.2. Garden Maintenance

- (a) Litter pick – Pick up litter and general waste (e.g. paper, bottles, plastic, cans and loose debris) from all garden areas. Sort and place in recycling bins provided by CSIRO on site
- (b) Garden clean-up – remove leaves, bark, twigs, branches, spent flower heads, dead/diseased plants and debris from garden beds and recycle at a registered facility off site
- (c) Pruning – trim plants, hedges and shrubs to maintain a compact form, free from wayward growth, whilst still maintaining a healthy and tidy appearance. Ensure a 200mm gap is maintained between plants and the surface of any structure. Ensure that shrubs and plants do not encroach onto pathways, roads or courtyard areas. Ensure that signage, lighting and garden features are not obstructed by plant growth. Trees to be kept clean trunked for a clear line of sight and tidy presentation. Recycle all green waste off site to a registered recycle facility.
- (d) Pest control – Inspect plants in garden areas for pests and treat with pesticides. Pesticides must comply with Australian Standards and be approved for use, in writing, by the CSIRO Facilities Contact. A record of chemical application will need to be kept and presented to the CSIRO Facilities Contact as part of all spraying events onsite
- (e) Weed control – remove all weeds from garden beds. Weeds below 300mm in height to be hand removed or sprayed out using an approved herbicide, above 300mm weeds must be removed by hand. Recycle all green waste off site to a registered recycle facility. Herbicides to comply with Australian Standards and be approved for use, in writing, by the CSIRO Facilities Contact. A record of chemical application will need to be kept and presented to the CSIRO Facilities Contact as part of all spraying events onsite.

1.5.3. Paths, Courtyards and Hard Stand

- (a) Litter pick – Pick up litter and general waste (e.g. paper, bottles, cans, etc.) from all paths, gravel/pebble areas, courtyards and hardstand areas. Sort and place in recycling bins provided by CSIRO on site
- (b) Cleaning – vacuum, sweep or blow all footpaths, gravel paths, gravel/pebble areas paved areas, courtyards, and hardstands to remove all leaves and debris. Leaves and debris to be collected and recycled off site, not blown onto nearby lawns or garden beds
- (c) Weed control – remove weeds by hand or with an approved herbicide. Chemical dyes must not be used in these areas. Recycle all green waste off site to a registered recycle facility. Herbicides to comply with Australian Standards and be approved for use, in writing, by the CSIRO Facilities Contact. A record of chemical application will need to

be kept and presented to the CSIRO Facilities Contact as part of all spraying events onsite.

- (d) Areas where blowers must not be used adjacent to CSIRO buildings will be advised on commencement
- (e) Monitor and advise CSIRO Facilities contact of hazards such as moss/slippery pathways that could create a slip hazards to pedestrians

1.5.4. Roadways and Carparks

- (a) Litter pick – Pick up litter and general waste (e.g. paper, bottles, cans, etc.) from all Roadways and Carparks areas. Sort and place in recycling bins provided by CSIRO on site
- (b) Cleaning – vacuum sweep or blow all roads and carparks to remove all leaves, plant debris, soil and silt. Leaves and debris to be collected and recycled off site, not blown onto nearby lawns and gardens. Blowing shall not occur where vehicles are parked and damage may occur.
- (c) Weed control – remove weeds by hand or with an approved herbicide (approved in writing by the CSIRO Facilities Contact. Chemical dyes must not be used in these areas. Recycle all green waste off site to a registered recycle facility. Herbicides to comply with Australian Standards and be approved for use, in writing, by the CSIRO Facilities Contact. A record of chemical application will need to be kept and presented to the CSIRO Facilities Contact as part of all spraying events onsite.
- (d) Storm water drainage - Check road sumps, grate drains, spoon drains, kerb and gutter areas. Remove any leaves, debris and soil if its reasonably practicable. Report any areas requiring plumbers attention to the CSIRO Facilities Contact.

1.5.5. HS&E Hazard Management

- (a) Survey the site for HSE hazards (e.g. suspended broken tree branches, dying unstable trees, unsafe walkways, missing drain covers, overflowing drains, chemical/fuel spills)
- (b) Ensure area is safe and if possible rectify any hazard immediately (e.g. removal of tree branches) or otherwise make temporary arrangements (e.g. erect a barricade). Keep a stock of barricade material (e.g. barrier tapes, witches hats, posts) readily available for this purpose.
- (c) Notify the CSIRO Facilities contact of relevant observations, actions and safety recommendations immediately via email by COB next business day.
- (d) Dispose of all tree material including trunks and large limbs as directed by the CSIRO Facilities contact
- (e) Survey Tree Health and Safety – All trees on site to be surveyed and identified in a written schedule of trees that has a reference number per tree, location details, both textually and graphically presented, once yearly, by a qualified arborist or tree surgeon for clearance to building structures, power lines, paths and roads. Inspect for damage, dead branches and disease and provide a written report to the CSIRO Facilities Contact with recommendations and pricing. Additional requirements may be required on a site-by-site basis, additional requirements will be advised by the Facilities Contact.
- (f) The contractor must review site and locale fuel load and manage to minimise risk of fire damage. All noted issues to be advised to CSIRO Facilities contact.

1.6. Seasonal Preparedness

- 1.6.1. CSIRO requires the Contractor undertake Seasonal Site Preparedness Audits as described in Item 1.6.4 and 1.6.5. The Contractor is to take a strategic and proactive approach to Seasonal Preparedness at each Site, providing timely and effective communications to the CSIRO Contract Manager or Facilities Coordinator on risks to be addressed and any preparation works required including quotes where services fall within the scope of services of this Contract. Failure to undertake this essential task may be considered as a serious default on the part of the Contractor.
- 1.6.2. The Contractor must provide the Services to ensure the existing fuel load in garden beds is continually decreased and an effective solution is implemented to eliminate the fire hazard of leaves blown into garden beds.
- 1.6.3. As part of the annual performance review of the Contract (refer Item 1.13), the Contractor shall report on their demonstrated effectiveness in delivering Services to achieve the fire hazard reduction requirement in Item 1.6.2.
- 1.6.4. Site Preparedness (Fire) Audits are required and at a minimum must follow the requirements below:
 - (a) Inspect site throughout and provide a written fire audit to the CSIRO Contract Manager or Facilities Coordinator prior to the start of the fire season
 - (b) Rectify identified issues from Fire Report if requested by the CSIRO Contract Manager or Facilities Coordinator
- 1.6.5. Site Preparedness (Storm) Audits are required and at a minimum must follow the requirements below:
 - (a) Inspect site throughout and provide a written fire audit to the CSIRO Contract Manager or Facilities Coordinator prior to the start of the storm season
 - (b) Rectify identified issues from Storm Report if requested by the CSIRO Contract Manager or Facilities Coordinator
- 1.6.6. Where applicable Site Preparedness (Bushfire) Audits are required and at a minimum must follow the requirements below and as provided in the Checklist which will be confirmed by the CSIRO Contract Manager or Facilities Coordinator.
- 1.6.7. Where applicable Site Preparedness (Floods) Audits are required and at a minimum must follow the requirements below and as provided in the Checklist which will be confirmed by the CSIRO Contract Manager or Facilities Coordinator.

1.7. Incident Response Periodic and Reactive Services

- 1.7.1. The services identified in this Item 1.7 will be required either periodically or when advised by the CSIRO Facilities Manager. The Services are subject to the Contracted Schedule of Rates for each of these services as provided in Annexure A - Pricing Response and Service Frequency:
 - (a) Monday to Friday 7.30am to 5.00pm
 - (b) Monday to Friday after hours 5.00pm to 7.30am
 - (c) Saturdays
 - (d) Sundays and Public Holidays
 - (e) Call out fee (if any)

Incident Response

- 1.7.2. Storm/wind damage – remove fallen trees, branches and dangerous limbs as requested by the CSIRO Facilities Contact. Trees and or branches to be removed within 24hrs if they are a HSE risk or in a high traffic area. If not a HSE risk, implement safety measures (e.g. barriers, tape, cones) to ensure safety until corrective action completed.
- 1.7.3. Storm/miscellaneous damage – remove or make safe [e.g. washed out refuse (soil, tanbark)] to ensure safety within 24hrs if they are a HSE risk or in a high traffic area. If not a HSE risk, implement safety measures (e.g. barriers, tape, cones) to ensure safety until corrective action completed.

Hand watering

- 1.7.4. Hand water shrubs and plants under heat stress as directed by the CSIRO Facilities Contact.

Replanting

- 1.7.5. Ad hoc replacement of plants removed from garden areas. Contractor shall consult and recommend the appropriate replacement before to replanting.

Mulching

- 1.7.6. Inspect and assess garden beds. Supply and install hardwood mulch to garden bed surroundings. Spread mulch to approximately 75mm thick and raked area to even level or as otherwise directed by the Facilities Contact

Tree Management

- 1.7.7. Trim branches and remove dead limbs, diseased /dead trees, highlighted in the tree survey report, as requested by the CSIRO Facilities Contact. Recycle all green waste and take offsite to a registered recycling facility, or as directed by CSIRO Facilities contact, mulch to be utilised on site
- 1.7.8. Remove fallen tree branches as a result of sickness or adverse weather conditions. Branches shall be mulched and redistributed to the site garden beds if it is reasonably practicable.
- 1.7.9. Pest control – treat diseased trees identified in the survey report with approved pesticides as requested by the Facilities Contact

Site Preparedness (Fire) Audits

- 1.7.10. Inspect site throughout and provide a written fire audit to the CSIRO Facilities Contact prior to the start of the summer fire season
- 1.7.11. Rectify identified issues from Fire Report if requested by the CSIRO Facilities Contact

Slashing

- 1.7.12. Undertake slashing to areas nominated by the CSIRO Facilities Contact to a height not greater than 150mm

1.8. Equipment

- 1.8.1. The Contractor will maintain a methodology relating to equipment maintenance and replacement. Service records and maintenance schedules must be provided if requested by CSIRO.
- 1.8.2. Equipment used on site must be suitable for the Services being performed and incorporate innovative sustainable solutions. It is CSIROs preference for contractors to use low-emission and electric equipment

- 1.8.3. No equipment, fuel or charging apparatuses are to be stored on site.

1.9. Staffing and Personnel

- 1.9.1. All contractor personnel and subcontractors must successfully complete the requirements below:
- (a) CSIRO Induction requirements
 - (b) Approved List of Personnel and Subcontractors including ABN's and emails
 - (c) Attendance Register
 - (d) Notify CSIRO of the removal of Contractor's Employees
 - (e) Management of authorised Personnel
- 1.9.2. CSIRO requires consistency in the Contractor's Personnel undertaking works onsite, high turnover of Personnel leads to Service disruption, increases risk and presents an administrative burden and therefore cost to CSIRO. CSIRO requires that the Contractor has in place an effective approach and program to both attract and retain qualified and experience personnel and further has an effective plan for personnel contingency at all levels.
- 1.9.3. The Contractor shall ensure they have appropriately qualified and experienced personnel to undertake horticultural and garden maintenance. Proof of qualifications and experience must be provided if requested by CSIRO. The Contractor must provide a detailed description of their qualifications and/or experience in horticultural and garden maintenance.
- 1.9.4. For qualifications, Contractor should identify all qualification achieved and the institution/s where each was completed. Proof of qualifications and experience must be available if requested by CSIRO
- 1.9.5. All personnel working on Site must have current police check which is obtained every 12 months. Reportable outcomes must be disclosed to CSIRO for review and decision with regard to suitability to work on Site. CSIRO retains the right to decline access to Site for personnel it deems as not suitable to perform Services on Site.
- 1.9.6. All personnel working on site will be required to wear a uniform which readily identifies them while they are on site. The Contractor company name or logo is to be displayed on the uniform.
- 1.9.7. The Contractor will maintain an effective service redundancy/contingency plan including their ability to manage staff absences, both planned and unforeseen (e.g. holidays and sick leave).
- 1.9.8. The Contractor is to avoid use of labour hire staff as a default part of their Contingency plan. Casual and labour hire staff are not exempt from personnel requirements in this Contract such as, but not limited to, experience, qualifications, inductions and police checks.
- 1.9.9. The Contractor is to maintain and report on a Staff turnover/retention and Contingency management KPIs on an annual basis which will form part of CSIRO's annual performance review of the Contract.
- 1.9.10. CSIRO would welcome apprentices as part of the proposed and ongoing on-Site team. The Contractor shall maintain a ratio of experienced and fully qualified staff to apprentices of no less than 2:1 to ensure an adequate supervision and training environment for apprentices and to reduce risk of incidents and incomplete services

1.10. Keys and Access Cards

- 1.10.1. Any access cards or keys issued by CSIRO to the Contractor's Personnel, the Contractor is required to be responsible for them; and maintain a register of all access card and keys issued, showing to whom and when they were issued, together with the receiving Personnel's signature confirming receipt.
- 1.10.2. Any access cards or keys issued to grounds maintenance Personnel must not be transferred to another person.

11.1. Prevention of Disturbance

- 1.11.1. When working near staff or near occupied parts or areas of the site or buildings, the Contractor is required to perform the services in a manner that does not disturb or adversely affect the occupants or their use of those parts or areas.
- 1.11.2. If works are being conducted that may create a disturbance, it is the requirement of the contractor and their personnel to notify CSIRO facility manager in advance

1.12. Standards and Certifications

- 1.12.1. The Contractor will be required to comply with all relevant Australian legislation and standards applicable to the equipment and services, which may include, but not be limited to:
 - (a) Australian Electrical Standards
 - (b) Work Health and Safety (WHS) / OHS Act Compliance
 - (c) Safe Work Method Statements (SWMS)
 - (d) AS/NZS ISO 45001 (Occupational Health & Safety Management)
 - (e) Height Safety Standards (AS/NZS 1891)
 - (f) Public Safety & Traffic Management (AS 1742.3)
 - (g) Chemical Application & Biosecurity Regulations
 - (h) AS 4373 (Pruning of Amenity Trees)
- 1.12.2. The Contractor is required to provide all relevant certifications prior to commencement and upon request by CSIRO staff.
- 1.12.3. It is the responsibility of the contractor to provide competent and qualified personnel subject to the job to adhere to all Australian standards.

1.13. Performance

- 1.13.1. The following Key Performance Indicators (KPIs) have been identified and will apply, as a minimum to the Successful Tenderers performance:
 - (a) performance against conditions of contract
 - (b) provision of accurate reports within agreed timeframes
 - (c) cost control within allocated budget
 - (d) quality of service delivery and performance
 - (e) ongoing evidence is to be provided to the CSIRO Facility Manager of necessary licences or permits (for staff and business operations) on commencement of the Services and within two weeks for any new or renewed licenses

- (f) ongoing evidence of the appropriate insurances.
- 1.13.2. The Successful Tenderer will be required to provide written reports on a monthly basis that cover at a minimum:
- (a) confirmation of regular services provided
 - (b) details of all requests for additional services
 - (c) performance against key performance indicators
 - (d) details of all complaints received in the period, action taken to address those complaints and whether the complaint has been satisfactorily resolved

Performance Assessment

- 1.13.3. The Services performed under the Contract by the awarded Contractor may be subject to a performance management framework consisting of:
- (a) regular meetings between the parties
 - (b) issues resolution
 - (c) quarterly performance reviews
 - (d) formal Contract compliance auditing
 - (e) annual performance reviews
- 1.13.4. CSIRO will take into consideration the results of the monthly performance reviews and any Contract compliance audits undertaken, in determining its options for any extensions to the Contract.
- 1.13.5. Service Level Agreements will be developed/agreed as part of Contract negotiations with the Successful Tenderer.

1.14. Reporting

- 1.14.1. The Contractor shall provide written reports via email in word or pdf format, on a quarterly basis that cover at a minimum of:
- (a) confirmation of regular services provided including hours per site
 - (b) details of all requests for additional services
 - (c) performance against key performance indicators
 - (d) details of all complaints received in the period, action taken to address those complaints and whether the complaint has been satisfactorily resolved
 - (e) a summary of incidents that have occurred on each Site in the reporting period
 - (f) Fuel Consumption - A quarterly report provided to the Facilities Manager or Coordinator, detailing:
 - i. Fuel Type
 - ii. Volume
 - (g) Chemical Usage - A quarterly report provided to the Facilities Manager or Coordinator, detailing:
 - i. Chemical type
 - ii. date applied

- iii. location of application
- iv. volume

- 1.14.2. The Contractor will be required to provide written reports on an annual basis that cover at a minimum:
- (a) a review of service delivery performance against key performance indicators
 - (b) a review of contract compliance
 - (c) a review of the effectiveness of the service delivery plan
 - (d) other reports as required by CSIRO

1.15. Meetings

Contract Governance Meetings

- 1.15.1. A senior member of the Contractor's team, typically the Contract Manager, is required to attend annual Contract governance meetings with CSIRO Representatives to discuss all relevant matters relating to the strategic objectives of the Contract, higher level strategic or business-related matters, and the status and quality of the contractual relationship generally.
- 1.15.2. Each governance meeting will be chaired by CSIRO, and CSIRO will provide secretariat requirements of the meeting i.e. prepare meeting agendas and minutes
- 1.15.3. At CSIRO's discretion change the frequency of these meetings may change. This change must be in writing from CSIRO's Contracts and Compliance Manager
- 1.15.4. Regular agenda items for the 6 monthly meetings will include, but is not limited to, discussion on
- (a) characteristics of the contractual relationship
 - (b) review of the previous three (3) quarterly Contractor Performance review reports in accordance Clause 1.14.3, Performance Assessment
 - (c) serious or higher-level issues, which either party considers have not been satisfactorily resolved.
 - (d) the findings of any formal Contract Compliance Audit, undertaken in the previous three months in accordance with Section 10, Contracts Compliance Audit

Ad Hoc Meetings

- 1.15.5. The Contractor is required to attend various meetings convened by CSIRO from time to time, and here deemed appropriate in the context of the Contractor's responsibilities, represent CSIRO as its maintenance services provider; or in terms of any benefits to CSIRO drawn from the Contractor's knowledge of the facilities, or industry knowledge and facilities maintenance expertise generally.
- 1.15.6. Examples of ad-hoc meetings include but are not limited to meetings with:
- (a) Any CSIRO representatives relating to any incidental matters as they arise in connection with the Contract
 - (b) any of CSIRO's stakeholders, other service providers, its consultants and agents etc
 - (c) HSE and Emergency Planning Committees
 - (d) project or works planning and management group meetings

- (e) meetings with other government agencies or representatives, including statutory and, or regulatory authorities etc

1.16. Service Delivery Plan

1.16.1. A Service Delivery Plan shall be developed by the Contractor and is subject approval by CSIRO. The Service Delivery Plan is to include at a minimum;

- (a) Maintenance Program
- (b) HSE Management Plan
- (c) Risk Management Plan
- (d) Service Levels
- (e) Meeting Schedule
- (f) Key Performance Indicators
- (g) Other inclusion as required by the CSIRO Contract Manager or Facilities Manager e.g.
 - i. Quality Assurance Plan
 - ii. Personnel names, qualifications, certifications, and contacts

1.16.2. The Service Delivery Plan will be monitored quarterly and reviewed at the annual performance review for effectiveness against the Contract requirements and the needs of CSIRO

1.17. Transition In / Transition Out

1.17.1. The Tenderer is to describe how they propose to transition-in from the current provider to CSIRO sites and set up the Service ready for operation on the commencement of this Contract.

1.17.2. Within 14 days from the Effective Date, the Contractor may be required to provide to CSIRO, for approval by CSIRO (acting reasonably), a comprehensive Transition-in Plan (TiP).

1.17.3. The TiP is required to include an agenda of tasks and actions, including:

- (a) the tasks to be completed and approved by CSIRO
- (b) any critical path tasks and sub tasks included in the TiP
- (c) who will be responsible for completing the tasks; and
- (d) priorities, timeframes and anticipated task completion dates.

1.17.4. The Contractor may be required to attend weekly meetings with CSIRO during each Transition-in period to consult with CSIRO, discuss and resolve any issues as they arise, brief CSIRO on progress, and submit any material for approval.

1.17.5. The Contractor may be required to appropriately resource the transition-in effort to ensure that all tasks are completed in accordance with the approved TiP.

1.18. Sustainable Procurement

1.18.1. CSIRO has set targets to achieve net zero scope 1 and 2 emissions by 2030, net zero supply chain emissions (scope 3) by 2050, and to divert 80% or more of our waste from landfill by 2030. In addition, CSIRO aim to maximise water efficiency on sites and lower consumption.

Tenderers Should provide:

- (a) A copy of their Sustainability and/or Environmental policies, and the organisation's environmental targets.
 - (b) Outline initiatives that the tenderer will implement at CSIRO sites to support CSIRO's sustainability goals and targets.
 - (c) Provide data or metrics relevant to energy, emissions or waste generated and water used relevant to this scope of works, where available.
- 1.18.2. The Contractor will submit its sustainability report to CSIRO annually which is to include the following;
- (a) Waste recovered through recycling and resource recovery processing in tonnes and as a percentage of total waste per annum.
 - (b) Water saving performance against agreed benchmarks
 - (c) Energy saving performance against agreed benchmarks

1.19. HSE Requirements

Specific Health Safety & Environment (HSE) Requirements

- 1.19.1. The Contractor will be required to survey the site for HSE hazards (e.g. suspended broken tree branches, dying unstable trees, unsafe walkways, missing drain covers, overflowing drains, chemical/fuel spills).
- 1.19.2. Ensure area is safe and if possible, rectify any hazard immediately (e.g. removal of tree branches) or otherwise make temporary arrangements (e.g. erect a barricade). Keep a stock of barricade material (e.g. barrier tapes, witches' hats, posts) readily available for this purpose.
- 1.19.3. Notify the CSIRO Facilities Manager of relevant observations, actions, and safety recommendations immediately and in writing by COB next business day.
- 1.19.4. Risk Management Plan and appropriate JSEA/SWMS submitted to CSIRO Facilities Manager prior to commencing any work on site.
- 1.19.5. Dispose of all tree material including trunks and large limbs as directed by the CSIRO Facilities Manager.
- 1.19.6. Comply with local council, State Government and Commonwealth laws, regulations, and safety codes, including but not limited to, Workplace Health and Safety, noise restrictions and workhour restrictions.

General Health Safety & Environment Requirements

- 1.19.7. The Contractor must provide evidence of current licences, registration, or certification where licencing, registration or certification is required for the performance of the contracted work (for example Arborist/Tree Surgeon, Climber certification, Horticulturalist).
- 1.19.8. The Contractor will be required to ensure that prior to the commencement of any Contract work, all persons employed or engaged by the Contractor (including sub-contractors) to perform work for CSIRO:
 - (a) have completed CSIRO General Induction and Site Specific Induction training within the previous two years

- (b) have provided CSIRO with evidence of a current licence for any work that requires a licence
 - (c) undertake a security check if requested.
- 1.19.9. The Contractor must ensure that prior to the commencement of any Contract work:
- (a) a Job Safety and Environment Analysis (JSEA) is prepared and provided to CSIRO for all tasks being undertaken as part of the Contract work
 - (b) a Safe Work Method Statements (SWMS) is prepared and provided to CSIRO for all high risk work being undertaken as part of the Contract work
 - (c) a HSE Management Plan is prepared and provided to CSIRO.
- 1.19.10. During the performance of all Contract work, the Contractor must provide supervision for all persons employed or engaged by the Contractor (including sub-contractors).
- 1.19.11. During the performance of all Contract work, the Contractor display appropriate signage and undertake precautions regarding pedestrian and traffic safety during servicing.
- 1.19.12. The level of supervision must be sufficient to ensure that all work is conducted in accordance with JSEAs, SWMSs or HSE Management Plans provided to CSIRO for the work being undertaken.

1.20. Supply Chain Integrity

- 1.20.1. Entities can take action to combat modern slavery in their operations and supply chains to protect against possible business harm and improve the integrity and quality of their supply chains.
- 1.20.2. Modern slavery is used to describe situations where coercion, threats or deception to exploit victims and undermine their freedom and is a violation of human rights. Practices can include human trafficking, slavery, servitude, forced labour, debt bondage, deceptive recruiting for labour and services, forced marriage and forms of child labour (i.e. slavery or hazardous work).
- 1.20.3. The [Commonwealth Modern Slavery Act 2018](#) came into force on 1 January 2019 and defines the meaning of Modern Slavery. The Act requires entities based, or operating, in Australia, which have an annual consolidated revenue of more than \$100 million, to report annually on the risks of modern slavery practices in their operations and supply chains (including those of entities it owns and controls), and actions to address those risks. As an Australian Government Agency, CSIRO must report on the risks of modern slavery in our operations and supply chains.
- 1.20.4. Tenderers may be required to respond to questions in relation to Modern Slavery. Further information can be found at <https://www.ag.gov.au/crime/people-smuggling-and-human-trafficking/modern-slavery>

1.21. Broader Economic Benefits to the Australian Economy

- 1.21.1. This RFT requires consideration of the Broader Economic Benefits to the Australian Economy. Further information can be found at: <https://www.finance.gov.au/sites/default/files/2020-08/consideration-of-broader-economic-benefits-in-procurement.pdf>.
- 1.21.2. Economic benefits to the Australian economy may be achieved when the goods or services being procured:

CSIRORFT2026019 - Ground Maintenance Services for CSIRO Managed Sites VIC Metro

- (a) Make better use of Australian resources that would otherwise be under-utilised
 - (b) Otherwise increase productivity
 - (c) Provides broader benefits that support the development and sustainment of industry capabilities.
- 1.21.3. An increase in productivity-enhancing technology development and adoption can also deliver economic benefit, for example through:
- (a) research and development related activities and investments (including those undertaken with universities)
 - (b) transfer of technology to Australian businesses such as through licensing arrangements for Intellectual Property
 - (c) Indigenous workforce participation
 - (d) engaging a business that provides services of persons with a disability
 - (e) traineeships or apprenticeships in areas of skills shortage; or
 - (f) boosting a tenderer's international competitiveness (e.g. through greater efficiency or product innovation).

1.22. Asbestos

- 1.22.1. The Tenderer warrants that no asbestos will be used in the manufacture of any component of the Goods, including any packaging, except as otherwise disclosed in this Tender.