



ADDENDUM 02 PMSB 25007 – C71

to the Request for Tender PMSB-25007-C71- Provision of Head Works Contractor – Konedobu, Port Moresby, Papua New Guinea released on 26/07/2026

DFAT provides the following information in accordance with the Standard Conditions of Tender.

No.	Question/Clarification	Response
1	Pricing Format	The required pricing format for the tender submission should be submitted as per requirements set out in the Request for Tender (RFT), Part 4, Attachment B
2	Is a construction methodology required as part of the tender submission?	Tenderers should provide their responses against the requirements set out in the Tender Response Form, located at Part 3 of the RFT, and include sufficient detail to demonstrate their capability, approach and understanding of the project where requested. Any methodology information should be incorporated within the relevant sections of the Tender Response Forms.
3	Is a detailed construction program required with the submission?	Yes, refer to Part 3 of the RFT.
4	Will the contractor be required to demobilise between project stages to accommodate tenant relocations?	Yes, Refer to Part 2 of the RFT – Scope of Requirements that contains indicative milestone dates.
5	Is there project duration or completion timeframes?	Yes, Refer to Part 2 of the RFT – Scope of Requirements that contains indicative milestone dates.
6	Do Liquidated Damages apply under the contract and, if so, the applicable rate and conditions?	Refer to the Part A of the Draft Contract
7	Are any additional documents or submission requirements not currently available on the tender portal?	All documents are available on the Tender portal.
8	Are there detailed drawings for all windows per block?	Window sizes specified in the schedule (refer AR-00835) are exclusive of installation tolerances. An allowance needs to be made to check on site all built dimensions. No detailed plans are available for issue.
9	As per document “PMSB-25007-C71 - HWC RFT - PART 2 - Scope of Requirements” 1.12.1.e. states “Removal and treatment of mouldy plasterboard walls and ceilings”.	Tenderers are advised that the intent of Clause 1.12.1(e) is to ensure the complete removal and remediation of mould-affected plasterboard and the underlying cause of mould growth. DFAT will accept either: - Removal and replacement of the entire affected plasterboard sheet; or - Removal (cutting out) and replacement of the mould-affected sections of plasterboard, provided the proposed approach achieves complete remediation of all mould-affected materials, addresses any underlying



		moisture ingress issues, and results in a compliant and fully restored finished surface. Tenderers should allow for all works necessary to achieve the above outcome and should include details of their proposed methodology within their tender submission. DFAT reserves the right to review and approve the final remediation approach during construction.
10	Please confirm whether the totals in each worksheet of the BOQ (apart from the "Summary" and "Work Rates" sheets) represent the refurbishment cost per individual house or the overall cost for all houses combined.	Tenderers are advised that the BOQ provided at Attachment B is an example/template only and has been included to assist Tenderers in presenting a detailed pricing breakdown. The BOQ expressly states that it is a template that should be adapted to suit the Tenderer's needs and contains indicative line items and quantities only. Tenderers are required to undertake their own due diligence when preparing their pricing. Tenderers are reminded that pricing submissions are to be provided in accordance with TRF 11 – Pricing Schedule and the requirements of the RFT documentation.
11	Please advise whether access will be provided to the DWG files to enable preparation to bring the design up to 'For Construction' documentation.	DWG files will be issued to the Head Works Contractor on Contract Award

12. Demolition Clarification

QUESTION: It states in the demolition plan that the ceilings are to be removed, but contrary information is provided in the Reflected Ceiling Plan, stating that the existing ceilings are to be cleaned, mould treated and painted. Could DFAT clarify on which is correct?

Reflected Ceiling Plan notes.

<u>CEILING NOTES</u>	
1. PREPARE ALL EXISTING PLASTERBOARD CEILINGS FOR NEW 3-COAT WHITE PAINT SYSTEM (PA.03), INCLUDING CLEANING, MOULD TREATMENT AND ERADICATION, MINOR REPAIRS, SANDING AND PRIMING AS REQUIRED, UNLESS OTHERWISE NOTED.	

Demolition Plan notes. (Showing the entire ceiling to be removed.)

	INDICATES EXTENT OF EXISTING FLOOR FINISHES, CEILING TILES AND GRID SYSTEMS AND TO BE DEMOLISHED
--	---



Australian Government

Department of Foreign Affairs and Trade

ANSWER: The Tenderers shall follow the following ceiling note as correct:

CEILING NOTES

1. PREPARE ALL EXISTING PLASTERBOARD CEILINGS FOR NEW 3-COAT WHITE PAINT SYSTEM (PA.03), INCLUDING CLEANING, MOULD TREATMENT AND ERADICATION, MINOR REPAIRS, SANDING AND PRIMING AS REQUIRED, UNLESS OTHERWISE NOTED.

The reference to ceiling tiles and grid systems within the demolition notes is **incorrect**. The hatching refers to the area for demolition of **existing floor surfaces only**.

13. Photos of Existing Electrical boards





All other information as set out in the RFT dated 09/07/2026 remains unchanged.

---End of Addendum No. 002---